

2016 Roadway Improvement Program, Sandown NH

The following is the scope of work for the 2016 Roadway Improvement Program which will commence during the summer months. Additional information will be provided as the project develops.

Part 'A' - The anticipated scope of Part 'A' work includes the reconstruction of a segment of Fremont Road, commencing near the intersection of Fremont Road and Sargent Road and extending approximately 7,818 linear feet to the Fremont Road and Main Street intersection. More specifically, Fremont Road improvement work shall include reclaiming the existing paved surface, supplementing the reclaimed stabilized base with crushed stone fine gradation (NHDOT 304.4), and re-paving 3-inches of hot bituminous asphalt pavement. Improvements shall also include several culvert replacements and construction and installation of headwalls, incidental grubbing and excavation, limited ledge removal, guardrail installation, loaming and seeding disturbed areas, and turf establishment.

Part 'B' – The scope of Part 'B' work generally consists of rehabilitating the existing bridge crossing of the Exeter River under Phillips Road. The critical bottom parts of the existing steel arch have deteriorated and thereby compromised the load bearing capacity of the bridge. Rehabilitation shall include building up the concrete footers on each side to above the rust line, providing solid anchors to both the existing footers and the steel arch. Work shall also include repairs to the upstream headwall, incidental grubbing and excavation, possible guardrail removal and replacement, loaming and seeding disturbed areas, and turf establishment.

An advertisement for bids is open until 3:00 pm on Thursday, June 16, 2016.

Please click on link below for full advertisement for bid.

http://www.sandown.us/Pages/SandownNH_WebDocs/RIP_2016.pdf